



# Status Update: Magdalena Ridge Observatory Interferometer

M. J. Creech-Eakman


New Mexico Tech – MROI Proj. Scientist

On behalf of the NMT and Cambridge Teams

# Magdalena Ridge Observatory


- Federally funded 2000-2011
- EIS completed in 2003
- Two facilities at MRO
  - Fast-tracking 2.4m
  - NIR/Optical 10-element interferometer
- 2.4m scope started full operations Aug, 2008
- 75% NASA/DoD funded

- MROI is 10 1.4m movable afocal telescopes in equilateral Y configuration
- Optical and near-IR operation
- Baselines from 7.8 to 340m
- Minimized reflections
- Design optimized for imaging mission



# MROI Key Science Mission


- AGN:
  - Verification of the unified model
  - Determination of nature of nuclear/extra-nuclear starbursts
  - $H = 14$  gives  $> 100$  targets.
- Star and planet formation:
  - Protostellar accretion, imaging of dust disks, disk clearing as evidence for planet formation
  - Emission line imaging of jets, outflows and magnetically channeled accretion.
  - Detection of sub-stellar companions.
- Stellar accretion and mass loss:
  - Convection, mass loss and mass transfer in single and multi-star systems
  - Bipolarity and collimation of circumstellar material, wind and shock geometries.
  - Pulsations in Cepheids, Miras, RV Tauris, etc.



# Requirements Flowdown

- Telescope diameter of 1.4 m
  - H magnitude = 14 for group delay tracking limit
- Spatial scales of 0.3 to 30 mas
  - Baselines from 7.8 to 340 m (for 0.6-2.4 microns)
- Moderate-to-high spectral resolutions
  - Separate fringe tracking and science cameras
- High throughput to achieve sensitivity limit
  - Fifteen reflections from primary to detectors
  - Optimized coatings for 0.6-2.4 microns
- Large number of telescopes
  - Optimized for model-independent imaging

# Walk through the Optical Path





# Unit Telescopes

- Designed/built by AMOS
  - 1.4m aperture
  - afocal alt-alt design
  - polarization preserving
  - 62 nm rms wavefront
  - UT1 expecting to ship later this year
  - UT2-3 ordered




# UT Enclosures


- Designed by EIE
- Builder selected
- Houses and transports UTs
- Allows close-packed configuration to 30 deg elevation without vignetting for 6 hour tracks




# Foundations and Beam Transport



July 2010






- Designed M3 and built by MRO
- Supports 3 UTs per beamline with 0.5 mbarr vacuum from UT to BCA
- Install for piers for inner array began 2010
- Houses all components of automated alignment system







# Automated Alignment System



cells and beam  
injection via  
fibers






# Beam Combining Facilities

- Design by M3/built KL House – delivered in 2008
- Thermal & vibrational stability
- Supports full array
- Single-pass DL section 190 m long



# Delay Lines



- Designed/built Cambridge
- Innovative approach
- Inductive pick-up & wireless communications
- DLI install to about 100m





# Science Instrument - SIRCUS

- MRO conceptual design
- J,H,K with  $R \sim 30$  and  $300$ ; studying higher  $R$
- One design: 4-way image plane combination with fast-switching to combine 6 beams in  $\sim 100$  sec




Mag	J	H	K
13	0.45	0.54	0.53
11	17.6	20.8	18.4
9	195	207	159

**Performance:**  
 SNR per spectral channel in 100 sec at  $R \sim 30$  with  $0.7''$  seeing and  $RN=5e-$

# Scientific Schedule for MROI

- Technical Phase – Key observations that quickly demonstrate technical competencies
- Science Phase – Scientific observations that produce transformational changes to understanding of astrophysical phenomena
- Open Time Phase – Release of facility to broader community through public funding



# Funding Issues



- No more earmarks\*
  - Currently operating on university funds
  - No anticipation of state educational bond this year
  - Pursuing other avenues
  - Expect to know more by SPIE
- 
- \* Earmarks may return in 2013

# New Website





# Thank you for your attention!

- PI: Van Romero
- Deputy PI: R. Cervantes
- Prog. Director: I. Payne
- System Architects: C. Haniff, D. Buscher
- Proj. Scientist: M. Creech-Eakman
- Proj. Manager: R. Selina
- NMT Team: V. Alvidrez, L. Archuleta, B. Brumley, C. Dahl, J. Deininger, P. DiBartolomeo, A. Farris, C. Jurgenson, R. King, D. Klinglesmith, T. McCracken, A. Meir, K. Miller, A. Olivares, R. Otero, J. Pino, C. Salcido, F. Santoro, A. Shtromberg, N. Torres
- Cam. Team: R. Boysen, J. Coyne, M. Fisher, B. Seneta, D. Sun, D. Wilson, J. Young



UNIVERSITY OF  
CAMBRIDGE